

SCP SERIES

STAGED CONTACTOR CONTROL PANELS

FEATURES

Standard range suitable for heater loadings up to 180kw

Standard electrical supplies are 380V, 400V, 415V, 440V, 3 Phase, 3 or 4 wire, 50 or 60 Hz. Special voltages are available.

Multiple stages.

IP55 Mild Steel Enclosures

Standard construction includes:

Door Interlocked Isolator

One contactor and one load MCB per stage.

“Top Hat” Timers for each subsequent stage

Indicators for “Power On” and “Heater Tripped”

Removable bottom entry gland plate.

The control panels are arranged for control by a single control thermostat. The contactors are fitted with stage timers, to bring on subsequent stages at timed intervals. Where a large number of stages are required it may be more economical to us PLC control instead of individual timers.

Panels can be custom built to meet customer specification