

SCP SERIES

STAGED CONTACTOR CONTROL PANELS

FEATURES

Standard range suitable for heater loadings up to 180kw

Standard electrical supplies are 380V, 400V, 415V, 440V, 3 Phase, 3 or 4 wire, 50 or 60 Hz. Special voltages are available.

Multiple stages.

IP55 Mild Steel Enclosures

Standard construction includes:

- Door Interlocked Isolator

- One contactor and one load MCB per stage.

- “Top Hat” Timers for each subsequent stage

- Indicators for “Power On” and “Heater Tripped”

- Removable bottom entry gland plate.

The control panels are arranged for control by a single control thermostat. The contactors are fitted with stage timers, to bring on subsequent stages at timed intervals. Where a large number of stages are required it may be more economical to us PLC control instead of individual timers.

Panels can be custom built to meet customer specification